GENERAL NOTES

- (E) EXISTING WINDOW, TO REMAIN
- (S1) REMOVE EXIST WINDOW, FILL WITH STUCCO PANEL WITH PLUSH INTERIOR SEE DET A6/5
- (S2) REMOVE EXIST WINDOW, FILL WITH STUCCO PANEL WITH RECESSED INT. SEE DET A6/5
- (L) EXISTING WINDOW REMOVED AND NEW LOUVER PROVIDED SEE DETAIL A6/7
- (B) INTERIOR HORIZONTAL VENETIAN BLINDS
- (G) EXTERIOR WINDOW GUARDS SHALL REMAIN AND BE REANCHORED AND PAINTED

ALL OPENINGS NOT MARKED OTHERWISE SHALL RECEIVE NEW WINDOWS SEE A6/6

FOR TREATMENT OF WINDOWS IN COURT SEE SECTIONS DRAWINGS A12 & A13 & SEE ALL PLANS

Date	Approved
3/17/72	
3.17.72	
3/17/72	
3/17/72	
3/17/72	
3/17/72	

Renovation of
Carnegie Library of Pittsburgh
Allegheny Regional Branch

Damianos and Pedone
Architecture
Interior Architecture
416 Hastings Street
Pittsburgh, Pennsylvania 15213
(412) 362-8422

EAST+NORTH ELEVATIONS

Revised
Date 3.17.72 · 7110 A8